BRUHAT BANGALORE MAHANAGARA PALIKE

DRAFT TENDER SCHEDULE

Name of Work: DRILLING OF BOREWELS INSTALLATION OF PUMP AND MOTORS, PROVIDING PIPELINE AND ADDITIONAL MOTOR PUMPS AND NECESSARY ACCESSORIES TO EXISTING BOREWELLS IN Ward no. 06

Sl. No.	Description	Unit	Quantity	Rates	
				In	In Words
1	Geophysical investigation of site for sinking borewell for supplying drinking water to the habitation either through the hand pump, MWS or P.W.S.S. by vertical electrical sounding by adopting venner or schlumbergers's method, including reconnaissance survey of geological formation, Geological investigation of existing ground water in vicinity, its quality, quantity & acceptability of the users indicating the location of site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 mtr in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site, engaging technical personal and labour required etc.complete as per specifications and direction of the Engineer in charge.	Each BW	41.00	1938.46	Rupees One Thousand Nine Hundred Thirty Eight and Forty Six Paise Only
2	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 0 to 50 m complete as per specifications and direction of the Engineer in charge.	Rmtr	2050.00	315.18	Rupees Three Hundred Fifteen and Eighteen Paise Only
3	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 50 to 100 m complete as per specifications and direction of the Engineer in charge.	Rmtr	2050.00	412.00	Rupees Four Hundred Twelve Only

Sl. No.	Description	Unit	Quantity	Rates	
				In	In Words
4	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 100 to 150 mcomplete as per specifications and direction of the Engineer in charge.	Rmtr	2050.00	458.35	Rupees Four Hundred Fifty Eight and Thirty Five Paise Only
5	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 150 to 200 m.complete as per specifications and direction of the Engineer in charge.	Rmtr	2050.00	484.10	Rupees Four Hundred Eighty Four and Ten Paise Only
6	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 200 to 250 m.complete as per specifications and direction of the Engineer in charge.	Rmtr	2050.00	560.32	Rupees Five Hundred Sixty and Thirty Two Paise Only
7	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 250 to 300 m.complete as per specifications and direction of the Engineer in charge.	Rmtr	2050.00	600.49	Rupees Six Hundred and Forty Nine Paise Only
8	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 300 to 350 m complete as per specifications and direction of the Engineer in charge.	Rmtr	2050.00	622.00	Rupees Six Hundred Twenty Two Only

Sl. No.	Description	Unit	Quantity	Rates	
				In	In Words
8	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 350 to above complete as per specifications and direction of the Engineer in charge.	Rmtr	2050.00	677.74	Rupees Six Hundred Seventy Seven and Seventy Four Paise Only
9	Supplying of ISI Mark 175 mm nominal bore medium black ERW casing pipe of 5mm thick black electric resistance continous welded midle steel tube material confirming to IS 1387/!993 and manufactured from hot rolled steel skelp/stripes in random length of 4 to 7 mtr both ends threaded confirming to IS 554/1985 one end(including of all taxes)complete as per specifications and direction of the Engineer in charge.	Rmtr	2460.00	1364.75	Rupees One Thousand Three Hundred Sixty Four and Seventy Five Paise Only
10	Providing and fixing 250mm dia PVC pipe and as per specification and directions.complete as per specifications and direction of the Engineer in charge.	Rmtr	410.00	1393.59	Rupees One Thousand Three Hundred Ninety Three and Fifty Nine Paise Only
11	175 mm dia M.S. Casing cap complete as per specifications and direction of the Engineer in charge.	Each	41.00	103.00	Rupees One Hundred Three Only
12	M.S. Casing pipe collars 'C' Class complete as per specifications and direction of the Engineer in charge.	Each	410.00	154.50	Rupees One Hundred Fifty Four and Fifty Paise Only
13	Fabricating supplying and mounting MS box of 16 SWG suitable for floor / wall mounting, fully weather proof with provision for better hear description, (providing with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primes paint and finally finished with approved colour enamelled metal paint etc,. complete box of 21600 sq cm complete as per specifications and direction of the Engineer in charge.	Sqm	902000.00	0.33	Thirty Three Paise Only
14	Labour charges for erection of new /repaired submersible pumpset along with GI pipes (32/50mm) cable (new submersible pumpset if required will be supplied by the department free of cost and released pump set should be handed over to department) including transportation (each length = 6.00m) complete as per specifications and direction of the Engineer in charge.	Per length	2050.00	92.00	Rupees Ninety Two Only
15	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete as per specifications and direction of the Engineer in charge.	No.	123.00	234.00	Rupees Two Hundred Thirty Four Only

Sl. No.	Description	Unit	Quantity	Rates	
				In	In Words
16	Supplying and laying of L.T.U.G Cable having aluminiumconductor PVC insulated shethed galvanised steel wire/ steel tape armoured cable with PVC outer sheathing 1.1 KV class 4 core 16 sqmm cable (confirming to IS 1554) complete as per specifications and Engineer in charge.	Mtr	1435.00	140.40	Rupees One Hundred Forty and Forty Paise Only
17	Digging of trenches of 0.6mm x 0.50 Mtrs wide refilling the trench to the required ground level and consolidating etc,. Complete sutting road surfaces complete as per specifications and Engineer in charge.	Mtr	1435.00	117.00	Rupees One Hundred Seventeen Only
18	Supplying and fixing Class-A GI Pipe on pole/ wall/drain crossing with necessary clamping arrangements for UG Cable of 1.1 KV class 40mm.complete as per specifications and Engineer in charge.	Mtr	82.00	294.58	Rupees Two Hundred Ninety Four and Fifty Eight Paise Only
19	Supplying and fixing wiring earth electrode for grounding conduits, IC cutouts and other equipments on the meter board using 40mm dia 2.90 mm thick GI pipe 2.5 mtr long buried in a pit,/ the pit should be filled with equal proportion of salt and charocal 150 mm alround the pipe to complete depth the connections from the pipe to the conduit etc,. is to be established though GI wire of size as per ISI specification 7.3.3 of ISI 732 using 12mm dia boalts, nuts washers and checknuts etc,. the pipe shall have 16 through holes of 122mm dia complete as per specifications and Engineer in charge.	No's	41.00	4317.00	Rupees Four Thousand Three Hundred Seventeen Only
20	Supply and fixing LT cast iron pot heads suitable for 1.1 KV class 16 sqmmUG cable filled with necessary bitumen/ insulating compound complete with terminals, clamps, bolts nuts and washers etc,complete as per specifications and Engineer in charge.	No's	41.00	280.00	Rupees Two Hundred Eighty Only
21	Supplying and fixing of polished wood board made of not less than 15mm thick plank on both sides with planks made out on not more than 2 pieces and fixing the same to wall using tapered inverted wooden plugs screws etc., Size 20 x 20 x 2.5 inches complete as per specifications and Engineer in charge.	No's	41.00	302.00	Rupees Three Hundred Two Only
22	Cleaning of bore well inciuding yield tetsting of borewell either using slow or fast rig for not more than 2 hours at the final depth with air compressor or suitable pump as per specification (PRED 12-13 SL NO.9.5 PAGE NO.49)complete as per specifications and Engineer in charge.	each	10	10128	Rupees Ten Thousand One Hundred Twenty Eight Only
23	Borewell Clamp Set complete as per specifications and Engineer in charge.	Set	41.00	1800.00	Rupees One Thousand Eight Hundred Only

Sl. No.	Description	Unit	Quantity	Rates	
				In	In Words
24	Supply & delivery at site brand new texmo/innoval/lubi/sabar /Atalanta/calamal/ waterman/Radha make suitable HP deep well submercible pumpset suitable for vertical installation in 150 dia borewells compressing of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water squirrel cagesubmercible induction motor suitable for operation of 3Ph, 50Hz.380/440 volts AC supply fitted with required accessories such as suction, casing, suction strainers, sand guard. Non return valve etc Complete the pump and motor shall from an integral unit with all the required fittings 17.5HP 30 Stage.complete as per specifications and Engineer in charge.	No	30.00	72126.00	Rupees Seventy Two Thousand One Hundred Twenty Six Only

Sl. No.	Description	Unit	Quantity	Rates	
				In	In Words
25	Supply & delivery at site brand new texmo/innoval/lubi/sabar /Atalanta/calamal/ waterman/Radha make suitable HP deep well submercible pumpset suitable for vertical installation in 150 dia borewells compressing of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water squirrel cagesubmercible induction motor suitable for operation of 3Ph, 50Hz.380/440 volts AC supply fitted with required accessories such as suction, casing, suction strainers, sand guard. Non return valve etc Complete the pump and motor shall from an integral unit with all the required fittings 20 HP 40 Stage.complete as per specifications and direction of the Engineer in charge.	Rmtr	21.00	90595.00	Rupees Ninety Thousand Five Hundred Ninety Five Only
26	Providing, laying & jointing GI pipes confirming to IS specification of approved make with fittings such as collars bends elbows tees nipples plugs with cuts threads using white lead & threads for joints wherever necessary as per direction including all lead & lift etc,. complete 'A' grade(excluding cost of fittings) 50mm dia GI pipe B Class.complete as per specifications and direction of the Engineer in charge.	No's	17085.00	415.00	Rupees Four Hundred Fifteen Only
27	Supply and fixing Heavy Collar for GI Pipes 50MM complete as per specifications and direction of the Engineer in charge..	Mtr	2296.00	180.00	Rupees One Hundred Eighty Only
28	Supplying of submersible pump cable 1X3X6..0 Sq.mm .complete as per specifications and direction of the Engineer in charge..	No.	35700.00	144.00	Rupees One Hundred Forty Four Only
29	Supplying & delivery at site brand new / Essen / Lotus sunsines/Adarsh/ Gk controls best indigenous make combine energy meter-cum-control panel board unit of size 1200 x 600 x 300 mm minimum mechanically strong and vermin and water proof the unit shall have two detachable doors suitable for operation on 3ph, 50Hz, 380/440 volts, AC supply with spring loaded latch locking with a key ribs should be provided inside the door , canopy apron and louvers ventilators shall be provided the combine energy mtr cum control panel board unit suitable for operation on 3ph, 50Hz, 380/440 AC supply shall be consisted etc,. completed T panel board shall be fabricated on single unit in the above components panel board for suitable pumpset above components panel board for suitable pumpset above Up to 20HP with star delta starter (MR) complete as per specifications and direction of the Engineer in charge.	No's	46.00	21000.00	Rupees Twenty One Thousand Only

Sl. No.	Description	Unit	Quantity	Rates	
				In	In Words
30	Supplying & delivery of brand 50mm Gate Valve. complete as per specifications and direction of the Engineer in charge.	No's	41.00	1800.00	Rupees One Thousand Eight Hundred Only
31	Supplying & delivery of brand 50mm Non Return Valve.complete as per specifications and direction of the Engineer in charge.	No's	41.00	1800.00	Rupees One Thousand Eight Hundred Only
32	Supplying and fixing MCB.complete as per specifications and direction of the Engineer in charge.	No's	41.00	900.00	Rupees Nine Hundred Only
33	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications and	Cum	6420.60	316.94	Rupees Three Hundred Sixteen and Ninety Four Paise Only
34	Providing and installing at site of work 63mm (0.662) PVC Pipes of 6 kg / cm2 including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not less than 15cms with gravel or selected earth available from the excavation etc.complete as per specifications and direction of the Engineer in charge.	Mtr	14268.00	394.32	Rupees Three Hundred Ninety Four and Thirty Two Paise Only
35	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications and direction of the Engineer in charge.	Cum	6420.60	128.26	Rupees One Hundred Twenty Eight and Twenty Six Paise Only

Assistant Engineer
Bruhat Bangalore Mahanagara Palike

Assistant Executive Engineer
Bruhat Bangalore Mahanagara Palike

Executive Engineer
Bruhat Bangalore Mahanagara Palike

"DTS Approved"

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಗಾಯಲಪಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ